


Ramboll's work Across Ukraine

03 JUNE 2025




PRESENTATION OVERVIEW





RAMBOLL GEOGRAPHICAL FOOTPRINT IN UKRAINE





KEY CHALLENGES

- OLD AND REDUNDANT EQUIPMENT
- DH LARGE HEAT LOSSES LEAKAGE
- FUEL SUPPLY
- HEAT METERING
- TARIFF STRUCTURE
- ONGOING WAR INFRASTRUCTURE DAMAGE
- RISK OF CORRUPTION
- FINANCING FUNDING
- COORDINATION



WAR IN UKRAINE – IMPACT ON THE SUPPLY SYSTEMS

Electricity

- Voltage fluctuations low voltage/high voltage
- Electricity supply according to the schedule
- Blackouts up to 72 hours

Gas supply

- Reduced pressure
- Loss of Gas supply

Water supply

- Reduced pressure
- No city water

*Photos from open sources









CONSULTANT CHALLENGES

- DATA COLLECTION
- **PROJECT MANAGEMENT (LOCAL PRESENCE / SITE VISITS)**
- TRAVEL DIFFICULTIES
- LANGUAGE BARRIERS
- FINANCING
- UNDERSTANDING THE CURRENT ENERGY SYSTEM
- UNDERSTANDING THE LOCAL LEGISLATION
- USING SUB-CONTRACTOR
- FEW CONTRACTORS AVAILABLE
- TIME MANAGEMENT



BOILER HOUSE CONSTRUCTION/REHABILITATION

Horishny Plavni

- Up to 90 MW complete rehabilitation
- Replacement of boilers, pumps, heat exchangers etc.
- Replacement of old burners in order to reach EU emission level









BIOFUEL BOILER HOUSE CONSTRUCTION



Lutsk DH project - Completed

- Capacity 5 MW
- Fuel: Wood chips

Zhytomyr DH project - Retendering

- Capacity 1.8 MWe, more then 8 MWth
- Fuel: Wood chips

Horishny Plavni DH project - Ongoing

- Capacity 7 MW
- Fuel: Sunflower Husk Pellets

Energy Efficient Rakivka - Tendering

- Capacity 4 MW
- Fuel: Agro Pellets





MOBILE BOILER HOUSES

Kremenchuk - Completed

- 10 Mobile Boiler Houses
- Fuel: Diesel, Natural gas
- BH capacity 3,9 MW, overall capacity 39 MW









DH NETWORKS REHABILITATION

- Acting as an Engineer under the FIDIC contract
- Approximate length of replaced networks across Ukraine: 8700 m trench





KYIV DISTRICT HEATING OWNER ENGINEERING

- Ramboll has recently been awarded the role of Owner's Engineer on an EBRD funded project
- Implementation Support and Works Supervision
- Supply and installation of around 100MW of electricity and around 100 MWt thermal CHP.
- Project period 2025-2029



One of existing CHP in Kyiv Source https://kte.kmda.gov.ua/



FEASIBILITY STUDIES

Mykolaiv Pre-Feasibility for a biomass power plant – On-going

- NEFCO funded project
- Evaluation of the biomass market, biomass types and availability
- Understanding of the current implemented and future projects in Mikolaiv
- Definition of the expected capacity of a potentially biomass CHP
- Recommended technology and evaluation of the main project risks

Lutsk Feasibility Study for a new construction of a power and \or heat generating - On-going

- Fact finding to define the current situation and market factors that will impact the techno-commercial analysis
- Verification of boiler capacity (desired heat output)
- Preliminary scoping of permitting, environmental and sustainability related aspects and impacts of the project including assessment on whether available biomasses meet EU's sustainability requirements.
- Techno-commercial analysis to define whether it's more advantageous to install a solid fuel fired steam boiler equipped with a steam turbine to enable generation of electricity in a CHP mode or a solid fuel fired hot water boiler for the production of heat only.



THANK YOU

Rasmus Stevns Nielsen, Project Manager – Sustainable Energy Planning

rnns@ramboll.com

